ENGINEERING DEPARTMENT.

MYSORE DIVISION.

Dated 22nd—25th June 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 5 P.M. on 27th July 1932, for Restoring Madalahalli Tank of Mullukatte Village, Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1000, in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Madalahalli Tank of Mullukatte Village, Nagamangala Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account thereafter.

Abstract estimate for restoring Madalahalli Tank of Mullukatte, Nagamangala Taluk:—

No.	Details of work	Per	Quantity
	I. Bund.		
1	Clearing the jungle on bund	Lump	sum
2	Cutting steps and grips where new bund is put up ...	,,	,,
3	Earthwork to bund with watering and tamping, etc., complete.	C.yds.	19,186
4	Turfing to slopes	Sqr.	781.04
5	Gravel backing to rough stone revetment with 1 mile lead	C.yds.	1,382
6	Rough stone work new with new jelly backing ...	,,	2,384
7	Rough stone work old removing and reveting the same with new jelly as per details in separate statement.	,,	185
8	Providing and fixing grade stones including cutting figures and painting.	No.	29
9	Providing and fixing Index stones	,,	29
10	Providing and fixing guage stone with cutting figures and painting, etc.	,,	1
11	Providing and fixing register number and date stone with figuring and painting.	,,	1
12	Providing B. M. stones with figuring and painting ...	,,	2
	II. Breach.		
1	Clearing sand silt, etc., from the breach	C.yds.	444
2	Earthwork excavating foundation in mixed soil ...	,,	40
3	Blasting rock	Lump	sum
4	Benching rock for core wall	S.ft.	672
5	Burnt brick in surki mortar	C.ft.	630
6	Plastering with surki mortar	Sqr.	9·81
7	Puddle	C.yds.	238
8	Earthwork filling in the breach with a mixture of 1—3 good gravel and 2—3 clay including wateriug, tamping and consolidating, etc., complete.	,,	3,259
9	Turfing to slopes	Sqr.	47·61
10	Gravel backing to revetment with one mile lead ..	Cyds.	148
11	Rough stone revetment new with new jelly backing ...	,,	283

No.	Details of work	Per	Quantity
	III. Sluice.		
1	Clearing site and levelling ground	Lump	sum
2	Benching rock	,,	,,
3	Earthwork excavating foundation	C.yds.	9
4	Concrete in surki	C.ft.	183
5	Burnt brick in surki mortar	,,	534
6	Burnt stone slabs 6″ thick dressed and fixed in surki mortar.	S.ft.	240
7	Surki plastering	Sqr.	7·84
8	Cutting holes in guide and orifice slab	Each	4
9	Providing wooden plug with iron rod and locking arrangement.	Lump	sum
	IV. Left Waste Weir.		
1	Earthwork excavating foundation and draft and approach clearing.	C.yds.	2,082
2	Concrete in surki mortar	C.ft.	687
3	Burnt brick in surki mortar	,,	1,278
4	Burnt stone slab 6″ thick, dressed and fixed in surki mortar	S.ft.	590
5	Surki plastering	Sqr.	21·58
6	Rough stone work new jelly filling	C.yds.	121
	Constructing a silt dam across the feeder halla just above contour line.	Lump	sum

Dated 22nd—25th June 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 5 P.M. on 27th July 1932, for Restoring Raghavapur Major Tank Regulation No. 4 of Gundlupet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 (one thousand) only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Rostoring Raghavapur Tank Reg. No. 4 of Gundlupet Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be cansidered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. On no account will the rates tendered be increased afterwards.

Abstract estimate for restoring Raghavapur Major Tank Registered No. 4 of Gundlu pet Taluk :—

Sl. No.	Items of work	Per	Quantity	Cost
1	Clearing Jungle and prickly-pear ...	Grade.	472/3	
2	Cutting grips in old bund ...	,,	42	
3	Earthwork to bund including watering and tamping with lead lift, etc.	Cyd.	5556	
4	New Stone Revetment ...	,,	879	
5	Gravel to top of bund including carting and consolidating	,,	262	
6	Turfing including carting, etc. ...	Sqr.	468·49	
7	Removing and refixing old grade stones including carving figures painting and numbering.	Each	20	
8	Preparing and fixing new grade stones with bed slabs in place of missing ones including cutting figures painting and numbering, etc.	,,	28	
9	Preparing and fixing Visavis stone ..	,,	48	
10	Preparing and fixing B. M. stones including carving figures, numbering and painting, etc.	,,	2	
11	Preparing and fixing date and Register No. stone including carving figure, painting and numbering, etc.	,,	2	
12	Preparing and fixing Gauge stone including carving figure, painting and numbering.	... L.S.		
13	Resetting revetment	... L.S.		
	Total ...	...	...	
	Breach No. I.			
1	Excavating and removing earth silt and sand in breach.	C.yd.	723	
2	Earthwork, excavating puddle trench and foundation of revetment and using to bund.	,,	103	
3	Puddle wall with gravel and clay ...	,,	429	
4	Earthwork to breach including watering and tamping with lead and lift (excluding quantity of puddle revetment and gravel backing).	,,	3164	
5	Gravel backing to revetment ...	,,	125	
6	New stone work (for breach portion) ...	,,	372	
7	Turfing including carting, etc., ...	Sqr.	68·60	
8	Jelly and transverse drains ...	... L.S.		
	Total ...	...	...	
	Breach Filling No. II.			
1	Excavating and removing silt earth and sand in Breach.	C.yd.	4665	
2	Excavting soft rock and earth for fundation of revetment dwarf walls, core walls and puddle walls.	,,	317	
3	Renching rock	S.ft.	200	
4	Burnt brick in surki mortar for dwarf wall.	C.ft.	1250	
5	New stone work with jelly ...	C.yd.	11	
6	Puddle wall with g ravel and clay ...	,,	1212	
7	Earthwork to breach including watering and tampering with lead and lift (excluding quantity of puddle, revetment and gravel back).	,,	9439	
8	Gravel backing to revetment ...	,,	460	
9	New stone work for revetment ..	,,	1173	
10	Turfing including carting, etc .	Sqr.	137·63	
	Total ..	...	...	

Sl. No.	Items of work	Per	Quantity	Cost
	IV. Sluice.			
1	Earthwork cutting bund	C.yd.	217	
2	Dismantling and removing revetment ...	,,	7	
3	Earthwork excavation	,,	34	
4	Concrete in surki mortar	C.ft.	562	
5	Burnt brick in surki mortar	,,	833	
6	Burnt stone slabs dressed and fixed (6") ...	S.ft.	299	
7	Cutting hole in the slab crifice and guide slab	Each	4	
8	Cement plastering ½" thick	Sqr.	0·69	
9	Cement pointing	,,	2·17	
10	Surki mortar plastering	,,	6·28	
11	Providing teakwood plug and rod with locking arrangements.	...	L. S.	
12	Filling with earth with watering and tamping	C.yd.	112	
13	Gravel backing behind revetment to existing bund.	,,	3	
14	Resetting old stone work with new jelly to existing bund.	,,	7	
15	Turfing	Sqr.	1·98	
	Total ...	...	..	
	V. Repairing the Existing Sluices.			
	Providing plug and rod with locking arrangements and patch repairs to masonry, etc.	Each	2	
	VI. Extending the Right Weir.			
1	Excavating soft rock mixed with earth ..	C.yd.	2,576	
2	Concrete in surki mortar	C.ft.	150	
3	Burnt brick in surki mortar	,,	296	
4	Burnt stone slabs dressed and fixed with pointing.	S.ft.	202	
5	Surki mortar plastering	Sqr.	0·50	
6	New stone work	C.yd.	19	
	Total ...	...	..	
	VII. Repairing the Existing Right Weir.			
1	Excavating soft rock	C.yd.	51	
2	Burnt brick in surki mortar	C.ft.	127	
3	Burnt stone slabs dressed and fixed with pointing.	S.ft.	101	
4	Surki mortar plastering	Sqr.	0·50	
5	Jelly wedging to existing apron and patch repairs to masonry.	...	L. S.	
6	New stone work	C.yd.	45	
	Total ...	...	..	
7	Improving the existing cart-track ...	...	L. S.	

K. NARAYANA IYENGAR,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 15th June 1932.

The attention of the public is invited to the notification, published in pages 633 and 634, of the *Mysore Gazette*, dated the 23rd June 1932, calling for tenders for the work of Restoring Tomatagere Hosakere, Registered No. 702 of Bowringpet Taluk.

The last date of the receipt of tenders is fixed on 18th July 1932.

C. T. NARASIMHA IYENGAR,
Executive Engineer.